

9-28

299
R

6-010767

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,650-00-00
E/2E/2 SE /4 SEC. 25, 10 S, 25 W
1320 feet from S section line
440 feet from E section line

Operator license# 3736 Lease Pfeifer well # 1-25

Operator: R.L.T. Investments County Graham

Address: St. Peter Rt. Well total depth 4077 feet 132.50
Morland, Kansas 67650 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 207 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Helberg Oil Company License# 5669

Address: Morland, Kansas 67650

Company to plug at: Hour: _____ Day: 28 Month: September Year: 91

Plugging proposal received from: Leon Pfeiffer

Company: R.L.T. Phone: _____

Were: Order 190 sx. cement - 60/40 pozmix - 6% gel. - 2 sx. flocele.
Heavy mud between all plugs. Pump cement down drill pipe.
Elevation 2461' - Anhydrite 2122' - 61' - Arbuckle No -
Top Dakota 1550' - 911' - 1211'.

Plugging Proposal Received by: Dale F. Balthazor
Plugging operations attended by agent? All , Part , None

Completed: Hour: 12:00A.M., Day: 28, Month: September Year: 91

RECEIVED
KANSAS CORPORATION COMMISSION

Actual plugging report:
1st plug 25 sx. @ 2160'.
2nd plug 100 sx. @ 1210'.
3rd plug 40 sx. @ 230'.
4th plug 10 sx. @ 40'.
15 sx. in Rathole.

OCT 8 1991
10-08-1991
CONSERVATION DIVISION
WICHITA, KS

Remarks: Cementing By: B.J. Titan.

INVOICED

I did / did not observe the plugging.

DATE 10-28-91
INV. NO. 33691

Jeb. S.

Dale F. Balthazor

(agent)
Form CP-2/3