

6 040151

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-22,014-00-00  
NE 1/4, SEC. 29, T. 10 S, R. 25 (W/E)  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9008  
Operator: Sunbelt Petroleum Co.  
Name & Address 734 N. 51st St. Ave  
Glendale, Arizona 85301

Lease Name Belleuve Well # 1-A  
County Graham  
Well Total Depth 4125 134.06 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 248' 260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Ranger Drilling Co. License Number 723  
Address Hays, Kansas

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from \_\_\_\_\_  
(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: Order 180 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk hulls and 8 5/8" plug.  
Spot with drill pipe with no less than 36 vis. mud between all plugs, with good  
circulation and no fluid loss.

\_\_\_\_\_ Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XX

Operations Completed: Hour: 10 AM Day: 6 Month: July Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 2200' w/200sks  
2nd plug @ 1300' w/100 sks and 1 sk hulls  
3rd plug @ 260' w/40 sks  
4th plug @ 40'-0 w/10 sks (Solid Bridge)  
10 sks in Rat Hole

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 16 1984  
07-16-1984  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Cemented by Sun  
(If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not) observe this plugging.

DATE 7-31-84

Signed Dennis L. Hamel July 13 1984  
(TECHNICIAN) 22

INV. NO. 2269 AUG 3 1984