

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22859-00-00
Spot: SESWSE Sec/Twnshp/Rge: 28-10S-22W
330 feet from S Section Line, 1700 feet from E Section Line
Lease/Unit Name: ARMBRISTER Well Number: 1
County: GRAHAM Total Vertical Depth: 3765 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: P.O. BOX 1469
PLAINFIELD, IL 60544

Conductor Pipe: Size feet: 8 1/2 2.36
Surface Casing: Size 8.625 feet: 209 w/150 sxs cmt
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 11/21/2002 9:30 PM

Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC

Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack. 8 5/8" wiper plug.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 11/21/2002 10:30 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 1760' w/25 sxs.
2nd. Plug at 1100' w/100 sxs.
3rd. Plug at 260' w/40 sxs.
4th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole w/10 sxs.

RECEIVED

NOV 27 2002

KCC WICHITA

11-27-2002

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 11-27-02

NO. NO. 200.3060868

NOV 25 2002