

6030528

API NUMBER 15-065-22,212-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

100' W. N.E. S.W. SEC. 26, T. 10 S, R. 22 W

990 feet from S section line

4390 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5114

Lease Name WEBSTER Well # 1

Operator: NATIONAL DEVELOPMENT CO.

County GRAHAM 128.87

Name & Address 205 E. CENTRAL, STE. 120

Well Total Depth 3965 feet

WICHITA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67202

Surface Casing: Size 8 5/8 feet 252'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DUKE DRUG. CO. INC. License Number 5929

Address GREAT BEND, KANSAS 67530

Company to plug at: Hour: PM Day: 19 Month: 7 Year: 19 85

Plugging proposal received from BILL DRANEY

(company name) DUKE DRUG. (phone) \_\_\_\_\_

were: 8 5/8 SET @ 252' CIRC. WITH HOLE FULL OF NO LESS THAN 36 VIS. MUD  
NO LOSS OR GAIN OF FLUID SPOT CEMENT PLUGS WITH DRILL PIPE.  
ORDER 190 SX. 60/40 PZ G GEL 3 1/2 CC 8 5/8 W.P.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:30 PM Day: 19 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P. @ 1759 BREAK CIRC. DISPLACE 2544.

CMT. MIX. LAYDOWN D.P. TO 850' DISPLACE 100 SX. CMT. MIX. + 1 SX. CELLO

FLAKE LAYDOWN D.P. TO 250' DISPLACE 40 SX. CMT. MIX. LAYDOWN

D.P. PUSH W.P. TO KELLY DEPTH FILL HOLE TO BASE OF CELLAR W/10 SX.

CMT. MIX. DISPLACE 15 SX. CMT. MIX. IN RATHOLE PLUG COMPLETE

Remarks: ELEV

(If additional description is necessary, use BACK of this form.)

I ( ) did / ( ) did not observe this plugging.

DATE AUG 06 1985

Signed Carl Goodrow  
(TECHNICIAN)

INV. NO. 9337

RECEIVED  
CONSERVATION COMMISSION  
AUG 5 1985  
08 05 1985  
CONSERVATION DIVISION  
Wichita, Kansas