

031486

1-31

199

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21095-00-00
NE NE NE, SEC. 4, T 10 S, R 23 WAE

4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Ninemire Well # 1

Operator: Energy three Inc.

County Graham 136.17

Name & Address Box 1505

Well Total Depth 4190 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 31 Month: Jan Year: 19 91

Plugging proposal received from Bill

(company name) Kelso (phone)

were: 8 5/8 set at 211 cwc 4 1/2 set at 4189 w/125 sks. PBDT 3985. Perfs 3830-34

34. Order sand common cement. Pull pipe. Order 250 sks 65/35 poz 10% gel
500 lbs. hulls. allied Cement Co. Wellbrock water trucks. Ran bailer to 1850.
Hole open.

Plugging Proposal Received by j Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30PM Day: 31 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 3780 w/4 sks common cement on sand w/bailer.

Recovered 1600 + First shot at 1850. Sq 8 5/8 w/ 150 sks 65/35 poz 10% gel
500 lbs. hulls to max psi 400 lbs. Close in psi 400 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1991
02-21-1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-25-91

INV. NO. 30858

J.G.S.

Signed Carl Goodrow
(TECHNICIAN)