

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03051-00-01  
Spot: NWNWNW Sec/Twnshp/Rge: 25-9S-19W  
4950 feet from S Section Line, 4850 feet from E Section Line  
Lease/Unit Name: BENOIT B Well Number: 1  
County: ROOKS Total Vertical Depth: 3569 feet

Operator License No.: 5058  
Op Name: CORSAIR ENERGY, LC  
Address: 914 E. DOUGLAS  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3564  
Surface Casing Size: 8.625 feet: 265

#115 99

Well Type: SWD UIC Docket No: D02917.0 Date/Time to Plug: 08/05/2003 8:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: JIM COLLINS Company: CORSAIR ENERGY, LC Phone: (316) 267-7779

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel with 1/4# flocele - 500# hulls.  
Tubing fish at 960'. Perf Dakota at 900'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/05/2003 11:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 960'.  
Spotted 100 sxs cement with 1/4# flocele - circulated at surface.  
POOH with tubing.  
Rigged up to 5 1/2" casing - squeezed 175 sxs cement with 400# hulls.  
Max. P.S.I. 600#. S.I.P. 400#.  
Rigged up to 8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls.  
Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED  
AUG 19 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Dennis J. Hamel  
(TECHNICIAN)

INVOICED  
DATE 8-19-03  
INV. NO. 2004060420

AUG 14 2003

BAY PETROLEUM CORPORATION

#1

BENIGIT B

25-9-19W  
NW NW NW

Contr.

ROOKS

County

E 2148

Comm. 3-10-49

Comp. 6-3-49

IP 101 BOPD

Tops	Depth	Datum
HEEB	3289	-1141
TOR	3308	-1160
LANS	3327	-1179
ARB	3564	-1416
T.D.	3569	-1421

Casing

8" 265  
5" 3564

ACID 500  
SWB 3 BOPH  
FMP 69 B0/24 HRS

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS
