

4-041795

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

9-6

API Number: 15-16<sup>B</sup> 01692-0000

SW NE NE 1/4 SEC. 25, 09 S, 19 W  
~~4290~~ ~~2970~~ feet from S section line  
~~980~~ ~~695~~ feet from E section line

KCCapB

Operator license# 5058

Lease: Baumgartner Well # 7

Operator: Griggs Oil, Inc.

County: Rooks 117.45

Address: 100 N. Main - Suite #1010  
Wichita, Kansas 67202

Well total depth 3614 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 160 feet  
w/125 sxs.cmt.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day 6 Month: September Year 1996

Plugging proposal received from: Wilbur Berg

Company: Griggs Oil, Inc. Phone: \_\_\_\_\_

Were: 5 1/2" casing set at 3614' w/100 sxs cement. Perf. at 3540' - 3373'.  
Perf salt at 2150' - Anhy. at 1575'. Squeeze at 1024' with 210 sxs cement.  
Ordered 275 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 13 1996  
9-13-96  
CONSERVATION DIVISION  
STATE CORPORATION COMMISSION

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour 1:30 P.M., Day 6, Month: September, Year: 1996

Actual plugging report: R.I.H. with tubing to 3383'. Spotted 10 sxs gel followed with 75 sxs cement with 300# hulls, followed with one barrell H2O. Pulled tubing to 2147'. Spotted 125 sxs cement with 200# hulls. Pulled tubing and squeezed with 50 sxs cement. Max. P.S.I. 1000#. 8 5/8" S.P. - squeezed 25 sxs cement down annulus. S.I.P. 100#.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD  . . . Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC , NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING , CASING \_\_\_\_\_ . Elevation: \_\_\_\_\_ GL

I did  / did not  observe the plugging.

*Dennis L. Hamel*  
(agent)

Form CP-2/3

INVOICED  
DATE 9-20-96  
INV. NO. 46529

DP