

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01689-00-00
Spot: SWNENE Sec/Twnshp/Rge: 25-9S-19W
4290 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: BAUMGARTEN Well Number: 4
County: ROOKS Total Vertical Depth: 3640 feet

Operator License No.: 5058
Op Name: CORSAIR ENERGY, LC
Address: 914 E. DOUGLAS
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3616
Surface Casing Size: 8.625 feet: 165

9 118³⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2003 8:30 AM
Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC
Proposal Rcvd. from: MIKE VONOSDALE Company: PLAINS INC Phone: (785) 798-3995

Proposed Plugging Method: Ordered out 330 sxs 60/40 pozmix - 10% gel - 18 sxs gel spacer - 500# hulls.
Junk in the hole.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/06/2003 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3582' - mixed and pumped 40 sxs cement with 300# hulls.
Pulled up to 3260' - pumped 18 sxs gel.
Pulled up to 1617' - circulated cement with 160 sxs cement with 300# hulls.
POOH. Topped with 40 sxs cement.
Hooked up to the annulus and pumped 75 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.

RECEIVED
OCT 14 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 10-14-03
NO. 2004060612

Form CP-2/3

OCT 09 2003

GRANT #1 **MAGICEP** #4

BAUMGARTEN

25-9-19W
SW NE NE

Contr. TRANS-ERA

ROOKS

County

E. 2201 Comm. 9-12-53 Comp. 11-20-53 IP 200 BOPD

Tops	Depth	Datum
AAK	E 1506	
HEEB	3331	-1130
TOR	3351	-1150
LANS	3371	-1170
ARB	3611	-1113
TD	3626	-1125

Casing
8" 165
5" 3616

DD 3626: 5 GOPH, NATL.:
ACID, 500: SWB 13 BOPH
5 HRS:

BAUMGARTEN POOL

DD TD
INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS