

To: 1 080035
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
120 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-055-21,489 00-00
NW SE SE, SEC. 22, T 23 S, R 34 XX
990 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT 4-18
Operator License # 5447

Lease Name Garden City S Well # 13
County Finney 159.25
Well Total Depth 4900 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1728

Operator: OXY USA INC.
Name & Address P.O. Box 26100
Oklahoma City, OK 73126-0100

Abandoned Oil Well Gas Well Input Well SWD Well O&A X
Other well as hereinafter indicated

Plugging Contractor VAL Energy Inc. License Number 5822
Address P.O. Box 322, Haysville, KS 67060

Company to plug at: Hour: 3 p.m. Day: 18 Month: 4 Year: 1996

Plugging proposal received from Skip
(company name) VAL Energy Inc. (phone) 316-522-1560

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1920-43'
1st plug at 2764' with 100 sx cement, 2nd plug at 1745' with 50 sx cement,
3rd plug at 900' with 25 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
KANSAS CORP
1996 APR 23
4-23-96
A. J. ...
OMI
X

Plugging Proposal Received by Kevin Strube
(TECHNICIAN) X

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:30 p.m. Day: 18 Month: 4 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 4700' with 25 sx cement,
2nd plug at 2900' with 100 sx cement, 3rd plug at 1740' with 50 sx cement,
4th plug at 900' with 25 sx cement, 5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE APR 24 1996
INV. NO. 45436
4-18

Signed Kevin D Strube
(TECHNICIAN) X

EFFECTIVE DATE: 4-13-96

State of Kansas

055-21,489

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

SGA? Yes X No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date April 14 1996

Spot East C.NW. SE. SE. Sec .22. Twp .23. S, Rg .34. X West

OPERATOR: License # 5447 Name: OXY USA INC. Address: P. O. Box 26100 City/State/Zip: Oklahoma City, Ok 73126-0100 Contact Person: Raymond Hui Phone: (405) 749-2309

990 feet from South XXXX line of Section 990 feet from East XXXX line of Section IS SECTION x REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Finney Lease Name: Garden City S. Well #: 13 Field Name: Sequoyah

Is this a Prorated/Spaced Field? X yes no

CONTRACTOR: License #: Undertermined at this time will report on ACO-1

Target Formation(s): Morrow

Well Drilled For: Well Class: Type Equipment:

- X Oil Enh Rec Infield Mud Rotary Gas Storage Pool Ext. Air Rotary OWWO Disposal Wildcat Cable Seismic; # of Holes Other

Nearest lease or unit boundary: 990 Ground Surface Elevation: 2941 feet MSL Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no Depth to bottom of fresh water: 340

Depth to bottom of usable water: 1020 Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: Length of Conductor pipe required:

If OWWO: old well information as follows:

Projected Total Depth: 4900 Formation at Total Depth: St Louis

Operator: Well Name: Comp. Date: Old Total Depth

Water Source for Drilling Operations: well farm pond X other

Directional, Deviated or Horizontal wellbore? yes X no

DWR Permit #: Will Cores Be Taken?: yes X no

If yes, true vertical depth:

If yes, proposed zone:

Bottom Hole Location:

Exp. 10/8/96

AFFIDAVIT 1040' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with 55-101, et. seq.

It is agreed that the following...

Pusher Skil SPUD DATE 4-10-96 INIT:GA LENGTH SURFACE PLANNED 85' @ 1720 + 1723 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. 1723 RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 3 1/2 @ 1722 CONDUCTOR ANHYDRITE T- 1722 B- 1723 ELEVATION TD 4900 FORMATION St Louis

RECEIVED KANSAS CORP COMM APR 23 11:07 AM 1996

TECHNICIAN KS DATE TYPE OF CEMENT 60/40/60 STARTING TIME 3:00 (AM/PM) DATE 4-13-96 COMPLETION TIME 7:30 (AM/PM) DATE 4-13-96 CEMENT COMPANY