

AL
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Landes Exploration Company & Franks Petroleum Company,

Complete Address P. O. Box #867, Magnolia, Arkansas.

Lease Name Knoll Well No. 1

Location SE-SE-NW Sec. 35 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 3828'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Hellar Drilling Company, Incorporated,

Address 1014 Union Center Bldg., Wichita, KS License No.

Operation Completed: Hour 11:00 AM Day 10 Month 7 Year 1969

The above well was plugged as follows:

216'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240'
to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 7/14/69

INV. NO. 89-4