

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dale Reese,

Complete Address 415 East Prescott, Salina, Kansas.

Lease Name Bittel Well No. 1

Location SE-SW-SE Sec. 11 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 4050'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kans. License No.

Operation Completed: Hour 3:30 AM Day 14 Month 2 Year 1972

The above well was plugged as follows:

234'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-17-72

INV. NO. 5181-W

Signed: M. L. Nichols
Well Plugging Supervisor