

KANSAS

*JL*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 21 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name John O. Farmer

Complete Address 370 W. Wichita, Russell, Kansas 67665

Lease Name ~~XXXXXX~~ Bittel Well No. 1

Location NW SE NW Sec. 11 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 3860'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 2:30 A Day 19 Month 7 Year 1972

The above well was plugged as follows:

RTD 3860' 8 5/8 csg set at 219' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 2200' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED  
DATE 7/21/72  
INV. NO. 6055-W