

15-179-20238-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Koch Exploration Company,
Complete Address Box #2256, Wichita, Kansas.
Lease Name Werth Well No. 1
Location SE-NE Sec. 15 Twp. 10 Rge. (E) (W) 26
County Sheridan Total Depth 4120'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Red Tiger Drilling Company,
Address 1720 Wichita Plaza Building, Wichita, Kans. License No.
Operation Completed: Hour 10:45 PM Day 28 Month 11 Year 1969

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 950'. Pulled DP to 250' and displaced 25 Sx. cement thru DP from
250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 12/2/69
INV. NO. 953-W