

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED
OCT 7 1969
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,
Complete Address Box #553, Russell, Kansas.
Lease Name Evergreen NW LKC Unit Well No. _____
Location SE-NW-SE Sec. 17 Twp. 9 Rge. (E) (W) 23
County Graham Authority 3945'
Total Depth RTD 3925
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Company, Incorporated,
Address Box #105, Chase, Kansas. License No. 1436
Operation Completed: Hour 11:00 AM Day 3 Month 10 Year 1969

The above well was plugged as follows:

185'--8 5/8" Surface casing, cement circulated with 150 Sx.
3825'--5 1/2" Production casing cemented on bottom with 125 Sx. Well Plugged back to
3903'. Hole filled with fiber glass tubing and junk to 1296'.
Squeezed well with 5 sacks hulls and 12 sacks gel initially and followed with 90 Sx.
cement from 1150' to 850' then 15 sacks gel from 850' to 250' and followed with 30 Sx.
cement from 250' to 150' then 3 sacks gel from 150' to 30' and finally 10 Sx. cement
from 30' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dickel

Well Plugging Supervisor

DATE 10/8/69INV. NO. 611-W