

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name Evergreen NW KC Unit Well No. 114-W

Location NW-SE-NW Sec. 17 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3860

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Halliburton Services,

Address: Box #339, Hays, Kansas. License No. _____

Operation Completed: Hour 6:00PM Day 29 Month 10 Year 1968

The Above well was plugged as follows:

220'--8 5/8" Surface casing, cement circulated with 150 Sx.
3858--5 1/2" Surface casing, cemented on bottom with 125 Sx. Well plugged back to 3836'.
Top perforations from 3684' to 3681'. 5 1/2" squeezed from Anhydrite to surface.

Attempted to run 2" tubing to bottom. Tubing stopped @ 25', styrofoam, wood and metal
had been dropped in well. After two days drilling on bridge was unable to get below
1980'. Hole stayed full of fluid which indicated bottom was plugged off. Ran 25 Sx.
cement @ 1980'. Pulled tubing to 1760' and circulated heavy gel mud using 8 sacks gel.
Pulled tubing to 1290' and displaced 60 Sx. cement using 2 sacks hulls in cement.
Pulled tubing to 245' and ran 10 Sx. cement. Pulled tubing and ran 5 Sx. cement to cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 10/31/68
INV. NO. 8733-W