

KANSAS

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-26-73
FEB 26 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sunflower Operating Company,

Complete Address Box #422, Eldorado, Kansas.

Lease Name Robinson A Well No. 464

Location SE-SE-NW Sec. 17 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3907'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:00 M Day 22 Month 2 Year 1973

The above well was plugged as follows:

183'--8 5/8" Surface casing, cement circulated with 150 Sx.
3906'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to
3902'. Top perforations from 3722' to 3724'.

Sanded well back to 3700' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(804') and squeezed well initially with 5 sacks hulls and followed with 110 Cu. Ft.
cement from 1100' to 775' then 14 sacks gel from 775' to 200' and followed with 30 Cu.
Ft. cement from 200' to 125' then 2 sacks gel from 125' to 40' and finally 10 Cu. Ft.
cement from 40' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in
pressure-150#. (Mudding and cementing operations by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/28/73
INV. NO. 7030-W

Signed: *A. L. Nichols*
Well Plugging Supervisor