

KANSAS

20

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-26-73
FEB 26 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sunflower Operating Company,

Complete Address Box #422, Eldorado, Kansas.

Lease Name Robinson A Well No. 11

Location SE-SE-NE Sec. 17 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3965'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:30 AM Day 22 Month 2 Year 1973

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 175 Sx.
3965'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3935'. Top perforations from 3784' to 3787'.
Sanded well back to 3700' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (705') and squeezed well initially with 5 sacks hulls and 7 sacks gel and followed with 110 Cu. Ft. cement from 1150' to 825' then 15 sacks gel from 825' to 225' and followed with 30 Cu. Ft. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure --250#. Final shut-in pressure--100#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. D. [Signature]*
Well Plugging Supervisor

INVOICED

DATE 2/28/73
INV. NO. 7031-W