

KANSAS

FORM CP-3  
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-179-20, 572-60-00

245 North Water  
Wichita, KS 67202

Operator's Full Name RAINS + WILLIAMSON OIL COMPANY, INC.

Complete Address 435 PAGE COURT - 220<sup>W</sup> / DOUGLAS - WICHITA, KS. 67202

Lease Name MC WILLIAMS Well No. #1

Location SE - SW - NE Sec. 23 Twp. 10 Rge. 26 (East) (West)

County SHERIDAN Total Depth 4119 FT

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor RAINS + WILLIAMSON OIL CO. INC (BOB. DELANEY)

Address 435 PAGE COURT 220<sup>W</sup> DOUGLAS - WICHITA, KS License No. \_\_\_\_\_

Operation Completed: Hour 6:15<sup>PM</sup> Day 24 Month NOV Year 1980

The above well was plugged as follows:

8 5/8" 292 FT SP. CUM. w/ 200<sup>ST</sup> 60/40 POZMIX - 2% GEL. - 3% PA-CL.  
ORDERED 105<sup>ST</sup> 50/50 POZMIX 6% GEL. + 8 5/8" PLUG. - EW. 2579 KB  
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.  
1<sup>ST</sup> PLUG. @ 1200 FT w/ 60<sup>ST</sup> CMT.  
2<sup>ND</sup> PLUG. @ 270 FT w/ 30<sup>ST</sup> CMT.  
3<sup>RD</sup> PLUG. → SOLID BRIDGE HULLS - PLUG. @ 40 FT to 0 w/ 10<sup>ST</sup> CMT.  
5<sup>TH</sup> IN RAT HOLE.

RECEIVED  
STATE CORPORATION COMMISSION  
CEMENTED BY SUN

NOV 26 1980

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Conservation Division Agent

DATE 12-11-80

INV. NO. 3726-W