

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Hinkle Oil Company,

Complete Address 1016 Union Center, Wichita, Kansas.

Lease Name McWilliams Well No. 1

Location NW-NE-NW Sec. 23 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 4085'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita, Plaza, Wichita, Kansas License No.

Operation Completed: Hour 8:00 PM Day 3 Month 11 Year 1972

The above well was plugged as follows:

257'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement
thru DP from 1275 to 950'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru DP
from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. D. [Signature]
Well Plugging Supervisor

INVOICED
DATE 11/9/72
INV. NO. 6609-W