

KANSAS

J
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-11-67
DEC 1 & 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Abercrombie Drilling, Incorporated & McClure Oil Company,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Zerr Well No. 1

Location SW-SE-NW Sec. 4 Twp. 10 Rge. (E) (W) 27

County Sheridan Total Depth 4084'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Aber Crombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 12:45 AM Day 7 Month 12 Year 1967

The above well was plugged as follows:

190'--7 5/8" Surface pipe, cement circulated with 135 Sx. (6 1/4" Hole).
Dakota section from 890' to 1070'.

Circulated hole with heavy mud. Pulled DP to 1090' and displaced 65 Sx. cement thru
DP from 1090' to 775'. Pulled DP to 170' and displaced 15 Sx. cement thru DP from
170' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/11/67
INV. NO. 6876-W

Signed: *W. L. D. [Signature]*
Well Plugging Supervisor