

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 20 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name L. J. Dreiling & Sons, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Zerr Well No. 1

Location CSE-SE Sec. 11 Twp. 10 Rge. (E) (W) 27

County Sheridan Total Depth 4100'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 12:30 AM Day 16 Month 4 Year 1970

The above well was plugged as follows:

210'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100 Sx. cement
thru DP from 1325' to 1000'. Pulled DP to 215' and displaced 25 Sx. cement thru
DP from 215' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 4/20/70

INV. NO. 1747-W