

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 6 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Rosen Oil Corporation,  
Complete Address 200 Sutton Place, Wichita, Kansas.  
Lease Name Zerr Well No. 1  
Location SE-NE-SW Sec. 11 Twp. 10 Rge. (E) (W) 27  
County Sheridan Total Depth 4100'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Gabbert-Jones, Incorporated,  
Address 830 Sutton Place, Wichita, Kansas. License No. \_\_\_\_\_  
Operation Completed: Hour 8:30 PM Day 27 Month 11 Year 1971

The above well was plugged as follows:

220'--8 5/8" Surface casing, cement circulated with 200 Sx.  
top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 110 Cu. Ft. cement  
thru DP from 1300' to 975'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 12/6/71  
INV. NO. 4490-W