

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Lindenman Well No. 1

Location NE-NE-NW Sec. 7 Twp. 10 Rge. (E) (W) 28

County Sheridan Total Depth 4181'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 12:00 M Day 18 Month 4 Year 1969

The above well was plugged as follows:

273'--7" OD Surface casing, cement circulated with 135 Sx. (6 1/4" Hole).  
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 65 Sx. cement thru  
DP from 1250' to 925'. Pulled DP to 300' and displaced 15 Sx. cement thru DP from  
300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichol  
Well Plugging Supervisor

DATE 4/21/69  
INV. NO. 9636-4