

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1989
01-26-1989

WELL PLUGGING APPLICATION FORM
(File One Copy)

CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 15-193-20,476 -0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Brito Oil Company, Inc. OPERATORS LICENSE NO. 4629

ADDRESS 200 E. First, Suite 208, Wichita, KS 67202 PHONE # (316) 262-8787

LEASE (FARM) Price WELL NO. 1-19 WELL LOCATION SE SE SE COUNTY Thomas

SEC. 19 TWP. 10S RGE. 32 ~~(S) (W)~~ TOTAL DEPTH 4700' PLUG BACK ID

Check One:

OIL WELL GAS WELL D & A X SWD or IWJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 322' CEMENTED WITH 205 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Circulate heavy mud in hole. 1st plug at 2650'
-25 sx. 2nd plug at 1800'-100 sx. and 1 sack Flocel. 3rd plug at 372'-40 sx. 4th plug at 40' with
wiper plug-15 sx. Rathole-15 sx. All cement 60/40 posmix, 6% gel, 3% cc.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACC-1 FILED? No
(If not, explain) Sent to operator for completion.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 4:15 p.m. on 1-12-89.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack H. Wharton
(Operator or Agent)

DATE: 1-24-89