

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-193-20,632-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Dunne Oil Co. KCC LICENSE # 4197

(owner/company name) ADDRESS 100 S. Main, Suite 410 CITY Wichita (operator's)

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 267-3448

LEASE Soucie WELL# 1-19 SEC. 19 T. 10S R. 32 (~~East~~/West)

- SW - SW - NE SPOT LOCATION/0000 COUNTY Thomas

2310 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2310 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 248.81 CEMENTED WITH 190 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3096/3101' T.D. 4700' PBDT 4699' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud, 1st plug at 2600' with 25 sks., 2nd plug at 1800' with 100 sks., 3rd plug at 300' with 40 sks., 4th plug

at 40' with 10 sks, 15 sks rathole, total 190 sks 60/40 pos, 6% gel, 1/4# flo seal per/sk. (If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Fisher PHONE# () 316-262-1841

ADDRESS 150 N. Main, Suite 801 City/State Wichita, Ks. 67202

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684

(company name) ADDRESS 150 N. Main, Ste 801, Wichita, KS PHONE # () 316-262-1841 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 12:30 a.m. 03-30-95

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 03-31-95 AUTHORIZED OPERATOR/AGENT: Jack H. Johnston

(signature) Vice President

RECEIVED
STATE CORPORATION COMMISSION
APR - 3 1995