

6-050164

8-16

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,566-00-00

NW SE /4 SEC. 6, 10 S, 31 W
1980 feet from S section line
1980 feet from E section line

Operator license# 5046

Lease Ostmeyer "A" well # 1

Operator: Raymond Oil Company

County Thomas

Address: P. O. Box 48788
Wichita, Kansas

Well total depth 4725 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 305 feet

153.56

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Raymond Oil Company Inc. License# 5046

Address: P. O. Box 48788, Wichita, Kansas 67201

Company to plug at: Hour: AM Day: 16 Month: August Year: 1995

Plugging proposal received from: Bill Schoenhofer

Company: Raymond Oil Company phone:

Were: Perfs at 4360' to 4370'. 5 1/2" casing set at 4620' with 650 sx.
Order 250 sx 60/40 poz, 10% gel, 500# hulls, 16 sx gel

RECEIVED STATE CORPORATION COMMISSION
AUG 21 1995
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Bruce Basye

Plugging operations attended by agent? All[XXX], Part[], None[]

Completed: Hour: AM, Day: 16, Month: August, Year: 1995

Actual plugging report: Pumped 3 sx 60/40 poz, 10% gel down 8 5/8" X
5 1/2" annulus. 300# shut in. Pumped 50 sx 60/40 poz, 10% gel with 300#
hulls down 5 1/2". Pumped 16 sx gel with 200# hulls down 5 1/2" casing.
Pumped 171 sx 60/40 poz, 10% gel down 5 1/2" casing, 500# shut in.

Remarks: Allied cementing on location

Condition of casing(in hole): GOOD XX BAD Anhy. plug: YES NO
Bottom plug(in place): YES XX, CALC XX, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING XX Elevation: 3068 GL

I did [XX] / did not [] observe the plugging.

Bruce D. Basye
(agent)

Form CP-2/3

INVOICED

DATE 8-28-95

INV. NO. 43368