

6 031534

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 20553 193-~~21553~~-00-00

NE NE SW, SEC. 6, T 10 S, R 31 W 7EX

2310 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30269

Lease Name Wiens Well # A 1  
County thomas 152.75

Operator: Argent Energy Inc.  
Name & Address 110 S. Main Suite 510  
Wichita, Ks. 67202-3745

Well Total Depth 4700 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_ x

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling License Number 5422

Address Wichita, Ks. 67202

Company to plug at: Hour: PM Day: 22 Month: april Year: 19 91

Plugging proposal received from Harold Maley

(company name) Abercrombie (phone) \_\_\_\_\_

were: 8 5/8 set at 287 w/200 sks cwc. Circ hole w/no less than 36 vis mud.

W/no loss or gain in fluids. Order 190 sks 60/40 poz 6% gel 3% cc.

Allied Cement Co.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN) x

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9.15PM Day: 22 Month: April Year: 19 91

ACTUAL PLUGGING REPORT

Spot plugs through drill pipe w/25 sks at 2650

100 sks at 1725 w/hulls

40 sks at 340

10 sks at 40 w/w.p.

Circ. 15 sks in rathole/w/joint of pipe.

Elev. 3073 Anhy 2631 - 64.

Remarks:

(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
06-07-1991  
JUN 07 1991

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 6-14-91

WV. NO. 32130

*File S.*

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow