

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21101-00-00  
Spot: N2SWNW Sec/Twnshp/Rge: 31-8S-17W  
3630 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: RUSS Well #: 9  
County: ROOKS Total Vertical Depth: 3420 feet

Operator License No.: 33190  
Op Name: NOBLE ENERGY, INC.  
Address: 100 GLENBOROUGH DR STE 100  
HOUSTON, TX 77067

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3412	0	w/125 sxs cmt
SURF	8.625	157	0	w/135 sxs cmt <u>111-15</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/03/2008 2:00 PM  
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.  
Proposal Rcvd. from: JAMES POMMEREHN Company: NOBLE ENERGY, INC. Phone: (785) 639-0830

Proposed Plugging Method: Ordered 440 sxs 60/40 pozmix - 4% gel - 800# hulls.  
DV Tool at 1302'.  
Operator elected all cement plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/03/2008 4:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3164' - pumped 225 sxs 60/40 pozmix - 4% gel with 500# hulls.  
Pulled tubing to 1796' - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls - had circulation to surface.  
Pulled all tubing - topped 5 1/2" casing with 15 sxs 60/40 pozmix - 4% gel.  
Verified cement to surface on backside.

Perfs:

**INVOICED**  
DATE 11-20-08  
INV. NO. 2009060767

Remarks: ALLIED CEMENTING COMPANY-TICKET #35068.

Plugged through: TBG

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 14 2008

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

NOV 12 2008

PKT

JOHN B. COLLINS  
 1007 CODY, SUITE A  
 HAYS, KS. 67501  
 CONTR DREILING OIL, INC.

REPLACEMENT CARD:  
 #9 RUSS

31-8-17W  
 C N/2 SW NW

CTY - ROOKS

GEOL LAWRENCE F. GRAY FIELD DOPITA

E 1998 KB CM 6/17/80 CARD ISSUED 8/14/80 IP OIL WELL  
 1993 GL ARB OH 3412-3425  
 SHAW(TOR) @ 3135  
 LKC 3194-3353 OA

+	+
+	+
+	+

API 15-163-21,101

SMP	TOPS	DEPTH	DATUM
ANH		1299	+ 690
TOP		2895	- 897
HEEB		3111	-1113
TOR		3133	-1135
LKC		3153	-1155
B KC		3375	-1377
ARB		3410	-1412
RTD		3425	-1427

8-5/8" 157/135sx, 5 1/2" 3412/125sx

NO DST'S  
 MICT - CO, (ARB OH), AC 2500 GAL,  
 PF 1/3353, 1/3329, 1/3311, 1/3240,  
 1/3194 & 1/3135, AC 8000 GAL, POP

INFO RELEASED: WAS OIL WELL - TIGHT  
 4/30/81

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS