

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21276-00-01
Spot: SENWNW Sec/Twnshp/Rge: 18-11S-22W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HARGER B Well #: 3
County: TREGO Total Vertical Depth: 3891 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1685		
PROD	4.5	3887	0	200 SX
SURF	8.625	178	0	140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2008 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2008 10:15 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto 4 1/2" - pumped 260 sxs cement with 400# hulls.
Max. P.S.I. 600#. S.I.P. 200#.
Tied onto backside - pumped 25 sxs cement.
Max. P.S.I. 50#.

Perfs:

Top	Bot	Thru	Comments
3454	3539		LKC
3438	3440		TORONTO

INVOICED
DATE 11-20-08
INV. NO. 2009060770

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 14 2008

Remarks: ALLIED CEMENTING COMPANY-TICKET #43960.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

(TECHNICIAN)

CM

PRT

Form CP-2/3

NOV 12 2008

replacement card

RITCHIE EXPLORATION
WICHITA KS 67202

Property of Ks Corp Comm

18-11S-22W
SE NW NW

#3 HARGER B OWWO

site: 4-1/2 N & 3-1/8 E OF WAKEENEY KS

dy: TREGO

API 15-195-21276

contr: UNKNOWN

field: HIXSON

prod: NONE

fr date 10/30/95

spc date 05/15/95

drig comp 05/15/95

card issued 10/30/95

test revised 12/02/96

•			



ELV: 2191 KB, 2186 GL LOG

tops.....	depth/datum
ANH.....	1657 + 534
B/ANH.....	1700 + 491
TOP.....	3203 -1012
HEEB.....	3416 -1225
TOR.....	3438 -1247
LANS.....	3453 -1262
BKC.....	3683 -1492
MARM.....	3773 -1582
PBTD.....	3840 -1649
LTD OLD.....	3889 -1698
RTD OLD.....	3891 -1700

IP status:
OIL, P 2.83 BO & 33.44 BWPD, SHAW 3438-3440, LKC
3454-3539 OA, 05/17/95
INFO RELEASED: 12/2/96 - WAS OIL WELL - TIGHT
HOLE
OLD INFO: OPERATOR WAS A SCOTT RITCHIE, 3
HARGER B, SPD 07/22/83, 07/31/83 8-5/8", OIL, P 37 BO
& 97, LKC 3454-3528 OA, 08/22/83 (CARD ISSUED
02/24/84)
CONTR: MURFIN DRILLING
NO CORES

COPYRIGHT 1998
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)