

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE-JE-SW, SEC. 12, T. 10 S, R. 32(W)E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6 070413

API NUMBER 15-192-20, 268-00P00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5275

Operator: Hillenburg Oil Co
Name & Address: 11600 S. Lynn Lane Rd.
Broken Arrow, OK 74011
David Hillenberg Jr

230 feet from S section line

2970 feet from E section line

Loose Name Howard Well # 1

County Thomas 153.23

Well Total Depth 4730 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____ Tag

Plugging Contractor White and Ellis Delg. License Number 5420

Address White & Ellis Delg., Inc.

Company to plug at: Hour: 6:00 PM Day: 28th Month: Oct Year: 1985

Plugging proposal received from Judy Steuber

(company name) White and Ellis Delg. (phone) 918-455-4444

were: 8 5/8" - 262 FT SP. cas. w/ 175 SK cmt., 6 1/4" Poz Gel - Ca-cl By Allied Cont.
Order 200 SK 60 1/4 Poz mix Gel - Ca-cl - 1 SK cello and 8 5/8" Plug

spot with Drill Stem, Recondition well (viscosity) heavy mud Between all plugs
Miss well, no circulation problems, mud condition, viscosity 48,
Weight 9.5, Water loss 10, Eht. 3065, Omb 2599

Plugging Proposal Received by Marion Schmidt (TECHNICIAN)

Plugging Operations attended by Agent? All _____ Part _____ None X

Operations Completed: Hour: 6:00 PM Day: 28th Month: Oct Year: 85

ACTUAL PLUGGING REPORT Ordered 200 SK 60 1/4 Poz mix Gel - Ca-cl - 1 SK cello and 8 5/8" Plug

spotted with Drill Stem, Reconditioned well, heavy mud Between all plugs
1st Plug @ 2610 ft. w/ 30 SK cmt., 2nd plug @ 1760 FT w/ 100 cmt
and w/ 4 SK cello, 3rd Plug @ 270 ft w/ 50 SK cmt.
4th Plug Solid Bridge @ 40 FT to 0 w/ 10 SK cmt.
10 SK In Pat. HLB (Circulate)

Remarks: Cemented by Allied Cont.

INVOICED RECEIVED (if additional description is necessary, use BACK of this form.)

DATE NOV 12 1985
INV. NO. 10961

NOV 4 1985
11-04-1985
CONSERVATION DIVISION
Wichita, Kansas

Signed Marion Schmidt (TECHNICIAN)
Boic