

8-23

288
R

6-050108

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,567-00-00

SW NE SW /4 SEC. 12, 10 S, 32 W
1650 feet from S section line
3630 feet from E section line

Operator license# 9067

Lease HOWARD well # 1

Operator: DAMAR RESOURCES INC.

County THOMAS

Address: P.O. BOX 70
HAYS, KANSAS 67601
913-625-0020

Well total depth 4708 feet ^{153.01}
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 inch @ 260 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: MURFIN DRILLING COMPANY License# 30606

Address: _____

Company to plug at: Hour: P.M. Day: 23 Month: AUGUST Year: 1991

Plugging proposal received from: RODNEY FARR

Company: _____ phone: _____

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2610 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1755 feet " 100 " Mousehole: 10 sacks

3rd plug @ 310 feet " 40 "

4th plug @ 40 feet " 10 " with 8 5/8" wiper plug

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1991
08-29-1991
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 11:30 pm, Day: 23, Month: AUGUST, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sk

Remarks: Elevation: 3052, Anhydrite: 2593-2625 feet, Arbuckle: NONE.

Did NOT penetrate Arbuckle, cemented by ALLIED CEMENTING COMPANY

I did[] / did not[X] observe the plugging. Marvin L. Miller

INVOICED

Marvin L. Miller P.I.R.T.II
(agent)

DATE 9-12-91

INV. NO. 33085

8-23

J. S.