

4 060114

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,526-00-00

SW SE NE, SEC. 17, T 10 S, R 32 W/EX

2970 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5248

Lease Name Sim Trust Well # 1

Operator: Olympic Petroleum Co.

County Thomas 152.91

Name & Address 2121 ^{SOC} Columbia Av.

Well Total Depth 4705 feet

Tulsa, OK 74114

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXX

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling License Number 5302

Address Wichita, KS

Company to plug at: Hour: 4:15PM Day: 14 Month: September Year: 19 90

Plugging proposal received from Pat Waggoner

(company name) Red Tiger Drilling (phone) _____

were: Order 190 sxs. 60/40 pos 6% gel 1/4# floccul persx.

Space all plugs through drill pipe with heavy drilling mud.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXXX

Operations Completed: Hour: 4:15PM Day: 14 Month: September Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2625' with 25 sxs. Anhydrite 2606-2645'

2nd plug at 1775' with 100 sxs. Dakota 1472-1772'

3rd plug at 395' with 40 sxs. Surface pipe to 342'

4th plug at 40' with 10 sxs. rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1990
10-03-1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing

(If additional description is necessary, use BACK of this form.)

INVOICED

I ~~XXXX~~ did not) observe this plugging.

DATE OCT 05 1990

INV. NO. 29550

Handwritten initials

Signed [Signature]
(TECHNICIAN)

Herb Deines