

6 050026

1-13

193-20,476 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

SE SE SE, SEC. 19, T 10 S, R 32 W/Ex

330 feet from S section line

390 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629 and 5267

Lease Name Price Well # 1-19

Operator: Brito Oil Co. Inc. K and E Petro  
Name & Address: 200 East First Suite 208  
Wichita, Ks. 67202

County Thomas 152.75

Well Total Depth 4700 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling Inc. License Number

Address Wichita, Ks.

Company to plug at: Hour: AM Day: 13 Month: Jan Year: 19 89

Plugging proposal received from Harold Maley

(company name) (phone)

were: Order 195 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with

fluid circulation and no fluid loss.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1989  
01-18-1989  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Bruce D. Basye (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 12:15AM Day: 13 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2650 w/25 sks Anhy

2nd plug at 1800' w/100 sks 1 sk F.C. Dakota

3rd plug at 372' w/40 sks

4th plug at 40' w/15 sks

15 sks in rathole

Remarks: Cemented by B. J. Titan

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 1-25-89

Signed Bruce Basye (TECHNICIAN) SMS

Bruce D. Basye

INV. NO. 23773

1-13