

3-31

4-071140

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,632-00-00

SW SW NE /4 SEC. 19, 10 S, 32 W
2310 feet from N section line
2310 feet from E section line

Operator license# 4197 Lease Soucie well # 1-19

Operator: Dunne Oil Company County Thomas

Address: 100 S. Main Well total depth 4700 feet
Suite 410 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 249 feet

152.75

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Abercrombie Drilling License# 30684

Address: 801 Union Center Building - Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 31 Month: March Year: 95

Plugging proposal received from: Gary Fisher

Company: Abercrombie Drilling Phone: 316-267-3448

Were: 8 5/8" - 249' S.P. cwc. w/190 sxs. 60/0 pozmix - 2% gel - 3% cc.
By Allied Cement. Elv.-3101' - Anhy.-2597' - Mud condition 49 vis. -
9.2 wt. - 9.6 waterloss - Chlorides 3200' at 4650'. No circulation
problems. Proposal 190 sxs. 60/40 pozmix - 6% gel - 1/4# Flocele per.
sack. Circulate hole - spot and displace all cement through drill pipe.
(Miss.Well). 1) 25 sxs. cement at 2600' - 2) 100 sxs. at 1800' -
40 sxs. at 300' - 10 sxs. at 40'. 15 sxs. in rathole (circulate)

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:30A.M., Day: 31, Month: March, Year: 95

Actual plugging report: Dunne Oil ordered 190 sxs. 60/40 pozmix - 6% gel-
and 1/4# Flocele per sack. Circulated hole - spotted and displaced
all cement through drill stem.

1st. plug at 2600' w/25 sxs. cement.
2nd. plug at 1800' w/100 sxs. cement.
3rd. plug at 300' w/40 sxs. cement.
4th. plug at 40' w/10 sxs. cement.
15 sxs. cement in rathole (circulated)

Remarks: By: Allied Cement.

Condition of casing(in hole):GOOD BAD Anhy.plug:YES NO
Bottom plug(in place):YES , CALC , NO Dakota plug:YES NO
Plugged through TUBING , CASING . Elevation: 3101 GE

I did did not observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1995
CONSERVATION DIVISION
WICHITA, KANSAS
(agent)

INVOICED
DATE 4-12-95
INV. NO. 42563