

6-090450

2-3

183
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,543-00-00

SW SW NW /4 SEC. 19, 10 S, 32 W
2970 feet from S section line
4950 feet from E section line

Operator license# 4629 Lease Soucie well #1-19

Operator: Brito Oil Company, Inc. County Thomas

Address: 200 East 1st, Suite 208 Well total depth 4700 feet ^{152.75}
Wichita, Kansas 67020 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 221 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie Drilling, Inc. License# 5422

Address: Wichita, Kansas

Company to plug at: Hour: PM Day: 1 Month: February Year: 1991

Plugging proposal received from: Harold Malley

Company: Abercrombie Drilling, Inc. phone: (316)262-1841

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2620 feet with 20 sacks Rat hole: 15 sacks

2nd plug @ 1800 feet " 100 " Mousehole: sacks

3rd plug @ 270 feet " 40 "

4th plug @ 40 feet " 10 "

5th plug @ feet

Plugging Proposal Received by: Ed Schumacher P.I.R.T. III

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:30 PM, Day: 3, Month: February, Year: 1991

Actual plugging report: Hole reported plugged as above.
Order 185sx 60/40 pozmix w/ 6% gel and 1 sx celloflake or flowcel.

Remarks: Elevation: 3101 GL, Anhydrite depth: 2600 - feet

Did Not penetrate Arbuckle, cemented by Allied Cementing Company

I did[] / did not[X] observe the plugging. Ed Schumacher

INVOICED

DATE 2-25-91

INV. NO. 30884

Ed Schumacher P.I.R.T. III
(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1991
02-21-1991

CONSERVATION DIVISION
Wichita, Kansas