

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-111-19010-00-00 1/25/1957
C-NE-NE-NE Sec/Twp/Rge 31-21-12 E
4950' feet from south section line
660' feet from east section line

61-75

TECHNICIAN'S PLUGGING REPORT

Operator License # 6470

Lease/Well# NUESSEN A5

County LYON

Operator: SCHANKIE WELL SER.

Well Total Depth 1900' feet

Name & 1006 SW BLVD P.O. BOX 397

Production Pipe: 5.5" Size Feet 1875'

Address MADISON, KS. 66860

Surface Casing: 8 5/8" Size Feet 86'

AB oil well XXXXXXX Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: SCHANKIE WELL SER. Lic. # 6470

Address: 1006 SW BLVD. P.O. BOX 397 MADISON, KS. 66860

Company to plug at: Hour: _____ Day: 25 Month: 8 2008

Plugging proposal received from: _____

Company Name: _____ Phone: _____

Were: 50' CEMENT PLUG @ 1800' 50' CEMENT PLUG @ 800' 150' CEMENT PLUG TO SURFACE.

Plugging Proposal Received by: MIKE HEFFERN

Plugging attended by Agent: All xxxxxxx Part _____ Technician None

Operations Completed: Hour: _____ Day: 25 Month: 8 2008

Actual Plugging Report: RAN TUBING TO 1800' PUMPED 15 SXS CEMENT, PULLED TUBING

OUT, SHOT CASING @ 800' PUMPED 15 SXS CEMENT, SHOT CASING @ 150' PUMPED 30 SXS.

CEMENT TO SURFACE, GEL SPACERS BETWEEN CEMENT PLUGS.

INVOICED

DATE 11-24-08
INV. NO. 2009060779

RECEIVED
NOV 17 2008

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I observe this plugging.

Signed: Mike Heffern
TECHNICIAN

KCC WICHITA

[Handwritten signature]