

6 070246

API NUMBER 15-167-22105-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NWSE-SE-SE, SEC. 3, T. 11 S, R13 WE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

ES 330440 feet from S section line
1125108 330440 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6029 Lease Name DAY TRUST Well # 1

Operator: LADD PETROLEUM County RUSSELL 116.71
Name & Address BOX 520
GREAT BEND, KANSAS
67530 Well Total Depth 3591 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor SUN CEMENTING CO. License Number _____

Address BOX 69 HAYS, KANSAS 67601

Company to plug at: Hour: 1:00 PM Day: 14th Month: NOV Year: 19 84

Plugging proposal received from PHIL EMIG

(company name) LADD PETROLEUM CO. (phone) 316-792-3571

were: 8 5/8" - 291 FT 50. CMC 1/200 SK CNT. - 4 1/2" CSG. SET @ 2182 FT 1/150 SK CNT.

D.V. TOOL SET @ 1004 CMC 1/300 SK CNT. - PLUG BACK T.D. 3140 FT

PERF'S - 2990 FT to 2996 FT, NO PIPE RECOVERY.

ORDER 190 SK 50/50 Pozmix 4% 3% GEL - CA-CL - 12 SK GEL - 4 SK HULL'S AND 1/2" PLUG.

PUMP IN ANNULUS BETWEEN 4 1/2" CSG AND 8 5/8" S.P. - ALSO PUMP INTO 4 1/2" CSG

WITH PUMP TRUCK Plugging Proposal Received by M. J. Schmidt
BOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:50 PM Day: 14th Month: NOV Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 190 SK 50/50 Pozmix 4% 3% GEL - CA-CL - 12 SK GEL,

AND 4 1/2" PLUG. PUMPEN IN ANNULUS 5 SK CNT. FULL OF CEMENT.

PRESSURED to 400 PSE -> PUMPED IN 4 1/2" CSG. 10 SK CNT. - 40 SK CNT 1/1 SK HULL'S.

8 SK GEL 1/1 SK HULL'S, 20 SK CNT. 1/1 SK HULL'S, RELEASED LIPPER PLUG.

AND PUMPED IN 115 SK CNT. - MAX. PRESURE 500 PSE RECEIVED

CEMENTED BY SUN. CEMENTING STATE CORPORATION COMMISSION

Remarks: NOV 26 1984

INVOICED (If additional description is necessary, use BACK of this form.)
I did not approve this plugging. 11-28-84
DATE

INV. NO. 4973 Signed M. J. Schmidt 11-21-84
BOIC (TECHNICIAN) 22