

4-071048

5-19

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-167-23,052-00-00

SE SW SW /4 SEC. 28 , 11 S, 14 W  
330 feet from S section line  
990 feet from E section line

Operator license# 30269

Lease Bar-S Ranch well # 1

Operator: Argent Energy, Inc.

County Russell

Address: 110 South Main  
Suite 510  
Wichita, Kansas 67202

Well total depth 3320 feet <sup>107.90</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 240 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Murfin Drilling Company License#     

Address: 250 N. Water - #300 - Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 19 Month: May Year: 93

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Company Phone: 316-267-3241

Were: 8 5/8" - 221' S.P. cwc. w/135 sx. 60/40 pozmix - 3% c.c. - 2% gel. By Allied Cement. Elv. 1799' - Anhy. 831' - K.C. Well.  
No ar buckle - Mud condition 45 vis. - 9.0 weight - 10.5 water loss.  
Proposal 170 sx. 60/40 pozmix - 6% gel. - circulate hole.  
Spot and displace all cement through drill pipe with heavy mud between all plugs. 25 sxs. @ 900' - 80 sxs. @ 525' - 40 sxs @ 240' - 10 sxs. @ 40'. 15 sxs. in rathole - circulate - cemented by Allied Cement.

Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 3:30P.M., Day: 19, Month: May, Year: 93

Actual plugging report: Murfin ordered 170 sxs. 60/40 posmix - 6% gel. Circulated hole. Spotted and displaced all clement through tubing with heavy mud between all plugs.  
1st. plug @ 900' w/25 sxs. cement.  
2nd. plug @ 525' w/80 sxs. cement w/F.C.  
3rd. plug @ 240' w/40 sxs. cement.  
4th. plug @ 40' w/10 sxs. cement.  
15 sxs. in Rathole (circulated)

Remarks: Cement by Allied Cement.  
Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING X, CASING     . Elevation: 1799 GL     

I did      and not X observe the plugging.

**INVOICED**

DATE 6-14-93

INV. NO. 32895

5-19

RECEIVED  
STATE CORPORATION COMMISSION  
6-9-1993  
JUN 9 1993  
CONSERVATION DIVISION  
Wichita, Kansas  
DH (agent)