


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

SHERIDAN County. Sec. 22 Twp. 10 Rge. (E) 28 (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner EMPIRE DRILLING COMPANY
Lease Name BETHELL Well No. 1
Office Address 650 FOURTH NATIONAL BANK BLDG. WICHITA, KS.
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JULY 13, 1958 19
Application for plugging filed JULY 13, 1958 19
Application for plugging approved JULY 13, 1958 19
Plugging commenced JULY 13, 1958 19
Plugging completed JULY 13, 1958 19
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well A. D. FABRICIUS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4435 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	SURFACE	0	166'	8 5/8"	166	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

BOTTOM PLUG @ 600' WITH 25 SACKS CEMENT
SECOND PLUG @ 160' WITH 15 SACKS CEMENT AND TOP PLUG @ 40' WITH 10 SACKS CEMENT



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 650 FOURTH NATIONAL BANK BUILDING WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, DAN J. KORNFELD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Handwritten Signature]

650 FOURTH NATIONAL BANK BUILDING
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of JULY, 19 58

My commission expires OCTOBER 21, 1958

[Handwritten Signature]
Notary Public.



LOG

COMPANY: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
 CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
 FARM: BETHELL # 1
 LOCATION: NW NW SW SECTION 22-10-28W, SHERIDAN COUNTY, KANSAS
 COMMENCED: JULY 1, 1958 ELEVATION: 2692 KB
 COMPLETED: JULY 13, 1958 POTENTIAL:

0	TO	167	SHALE AND SAND
167	TO	1805	SHALE AND SHELL
1805	TO	2217	SHALE AND SAND
2217	TO	2244	SHALE AND SHELL
2244	TO	2280	ANHYDRITE
2280	TO	2545	SHALE AND SHELLS
2545	TO	2680	SHALE
2680	TO	2910	SHALE AND SHELLS
2910	TO	3065	LIME AND SHALE
3065	TO	3190	SHALE AND LIME
3190	TO	3280	LIME AND SHALE
3280	TO	3420	SHALE AND LIME
3420	TO	3775	LIME AND SHALE
3775	TO	4027	LIME
4027	TO	4130	LIME AND SHALE
4130	TO	4163	SHALE
4163	TO	4230	SHALE AND LIME
4230	TO	4290	LIME AND SHALE
4290	TO	4339	SHALE
4339	TO	4391	SHALE, LIME AND CHERT
4391	TO	4435	LIME AND CHERT
		4435	RTD
			D & A

SET: 8 5/8" 166' WITH 125 SACKS CEMENT

TOPS:	HEEBNER	3766
	TORONTO	3788
	LANSING KANSAS CITY	3808
	BASE OF KANSAS CITY	4058
	CHEROKEE GROUP	4266
	MISSISSIPPIAN	4360

CONSERVATION DISTRICT
 WICHITA, KANSAS


CERTIFICATION

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE BETHELL # 1, NW NW SW SECTION 22-10-28W, SHERIDAN COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 21ST DAY OF JULY, 1958

Lucille Harr
 LUCILLE HARR, NOTARY PUBLIC



MY COMMISSION EXPIRES OCTOBER 21, 1958

PLUGGING
 FILE SEC 22.10 R 28W
 BOOK PAGE 115 LINE 43