


15-179-00079-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 25 Twp. 10S Rge. 29 (X) W (X)
Location as "NE/CNW%SW%" or footage from lines SW SW NW
Lease Owner Bell Oil and Gas-Transit Corporation
Lease Name Schmidtberger Well No. 1
Office Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) D and A
Date well completed September 5, 19 58
Application for plugging filed September 5, 19 58
Application for plugging approved September 5, 19 58
Plugging commenced September 5, 19 58
Plugging completed September 5, 19 58
Reason for abandonment of well or producing formation No production

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A D. Fabricius, Box 731, Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	223'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 600'; set plug cemented with 20 sacks of cement.
Filled hole with heavy drilling mud to 210'; set plug cemented with 20 sacks of cement.
Filled hole with heavy drilling mud to 40'; set plug cemented with 10 sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Paul E. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul E. Gathers

SUBSCRIBED AND SWORN to before me this 12th day of September 19 58
My commission expires May 17, 1962

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas

SEP 24 1958 Notary Public.
09-24-58
CONSERVATION DIVISION
Wichita, Kansas



PLUGGING
FILE SEC 25 T 10 R 29 W
BOOK PAGE 129 LINE 40

DRILLER'S WELL LOG

Bell Oil and Gas-Transit Corporation - Schmidtberger # 1 located in
SW SW NW Sec. 25-10S-29W,
Sheridan County, Kansas

Commenced: August 21, 1958
Completed: September 5, 1958
Elevation: 2760 K.B.

Casing 8 5/8" @ 223'
Cemented w/175 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Surface clay	0	30
River sand	30	125
Shale	125	219
Shale and shells	219	1280
Sand	1280	1500
Shale, shells and pyrite	1500	1715
Shale and shells	1715	1877
Anhydrite	1877	1911
Red bed	1911	1950
Red bed and sand streaks	1950	2120
Red bed and shale	2120	2318
Anhydrite	2318	2352
Shale	2352	2570
Shale and lime streaks	2570	2770
Shale	2770	2985
Pyrite	2985	3003
Shale and lime	3003	3275
Lime	3275	3335
Lime and shale	3335	3490
Shale and lime	3490	3805
Lime and shale	3805	3985
Lime	3985	4040
Lime and shale	4040	4075
Lime	4075	4118
Lime and shale	4118	4460
Lime and chert	4460	4533
Miscellaneous chert	4533	4550 TD

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.


Subscribed and sworn to before me
this 12th. day of September, 1958.

My Commission expires May 17, 1962.

TRANSIT CORPORATION

By Paul E. Gusten

Muellem Don
Notary Public



RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE SEC	25 T. 10 R. 29 W
BOOK PAGE	129 LINE 40