


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 7 Twp. 10-S Rge. 30 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Theodore Gore
Lease Name Rehmer Well No. 1
Office Address 650 Fourth National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed NOVember 6, 1959 19
Application for plugging filed November 6, 1959 19
Application for plugging approved November 6, 1959 19
Plugging commenced November 6, 1959 19
Plugging completed November 6, 1959 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4660 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
	<u>Sand-Shale</u>	<u>0</u>	<u>223</u>	<u>8 5/8"</u>	<u>216'</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 500' with 20 sacks cement
Plug set at 210' with 20 sacks cement
Plug set at 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
650-4th National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 1959
Lucille H. Harr
Lucille H. Harr Notary Public.

My commission expires October 21, 1962



LOG

COMPANY: Theodore Gore
 CONTRACTOR: Empire Drilling Company
 FARM: Rehmer
 LOCATION: NE NE SW of Section 7-10S-30W, Sheridan County, Kansas
 COMMENCED: October 25, 1959 ELEVATION: 2956 KB
 COMPLETED: November 6, 1959 POTENTIAL: D & A

0	to	223	Sand-Shale
223	to	2410	Shale-Shells
2410	to	2533	Shale
2533	to	2563	Anhydrite
2563	to	2630	Shale
2630	to	3115	Shale-Shells
3115	to	3340	Shale-Lime
3340	to	4010	Lime-Shale
4010	to	4295	Lime
4295	to	4435	Lime-Shale
4435	to	4480	Shale-Lime
4480	to	4511	Lime-Shale-Chert
4511	to	4555	Lime-Shale
4555	to	4610	Shale-Lime
4610	to	4629	Lime-Mississippian
4629	to	4660	Lime
4660			Rotary Total Depth

SET: 216' 8 5/8" casing with 125 sacks cement


ELECTRIC LOG TOPS:

Anhydrite	2530	+ 426
Topeka	3756	- 800
Heebner	3974	-1018
Toronto	3998	-1042
Lansing	4017	-1061
Base Kansas City	4306	-1350
Cherokee Group	4449	-1493
Basal Pennsylvanian Shaly Conglomerate	4575	-1619
Mississippian	4606	-1650
Schlumberger Total Depth	4657	

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 24 1959
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Rehmer # 1, NE NE SW of Section 7-10S-30W, Sheridan County, Kansas, as reflected by the files of Empire Drilling Company.


 Dan J. Kornfeld

SUBSCRIBED AND SWORN to before me, a Notary Public within and for Sedgwick County, Kansas, this 23rd day of November, 1959.




 Lucille H. Harr, Notary Public

My Commission expires October 21, 1962.