


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Sheridan County, Sec. 31 Twp. 10 Rge. (E) 29 (W)
Location as "NE/CNW/SW" or footage from lines NE SE SE
Lease Owner Sun Oil Company
Lease Name Project #3 (Strat Hole) Well No. 3
Office Address Box 3383, Tulsa, Oklahoma 74101
Character of Well (completed as Oil, Gas or Dry Hole) Strat Test
Date well completed 11-26- 19 67
Application for plugging filed 11-26- 19 67
Application for plugging approved 11-26- 19 67
Plugging commenced 11-26- 19 67
Plugging completed 11-26- 19 67
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Bill Nichols
Producing formation None Depth to top Bottom Total Depth of Well 2029 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrison	salt water	1942	2029	7"	319	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full 10# mud:
Placed 85 sacks 50-50 Pozmix, 6% gel, plug, 1150-1575'
Placed 20 sacks 50-50 Pozmix, 6% gel, plug 230- 330'
Placed 5 sacks 50-50 Pozmix, 6% gel, plug 0- 5'
Placed 10 sacks 50-50 Pozmix, 6% gel, plug in rathole.


Job completed 11-26-67 (Sun representative Mr. Jim Woods)

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss.
J. H. Allen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. H. Allen*
Box 3383, Tulsa, Oklahoma 74101
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of November, 19 67
My commission expires June 24, 1968



Received
KCC
12-8-67

DRILLERS' LOG

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1967
CONSERVATION DIVISION
Wichita, Kansas

Sun Oil Company
Project Well No. 3
SE/4 Section 31-10S-29W
Sheridan County, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Clay, shale, sand	0	368
Sand	368	860
Shale w/sand & lime strks.	860	1100
Sand	1100	1174
Shale	1174	1245
Sand (Top Dakota 1245')	1245	1350
Sand & shale	1350	1818
Shale & sand	1818	1944
Sand	1944	1988
Shale w/strks sand	1988	2029

Spudded November 23, 1967
T.D. 2029' November 25, 1967
Surface casing 7" at 319' w/120 sacks.

DST 1942-2029' recovered salt water.

I hereby certify that the foregoing is a true and correct copy of the Project No. 3 well log as recorded on the books of Sun Oil Company, Tulsa, Oklahoma.

J. H. Allen

J. H. Allen

STATE OF OKLAHOMA) SS
COUNTY OF TULSA)

Subscribed and sworn to before me this 7th day of December, 1967.

Doris Sutter

Notary Public

