

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20865-000

LEASE NAME Beckman "D"

WELL NUMBER 3

330 Ft. from S Section Line

3680 Ft. from E Section Line

SEC. 31 TWP. 10S RGE. 30 (E) or (W)

COUNTY Sheridan

Date Well Completed 9/15/86

Plugging Commenced 1/8/03

Plugging Completed 1/8/03

FEB 03 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS PO Box 783188 Wichita, KS 67278-3188

PHONE# (316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/8/03 (date)

by Darrel Dippman (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation L/KC, Myrick Depth to Top 4045' Bottom 4466' T.D. 4650'

Station, Conglomerate Sand
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
L/KC	Oil & Brine	4013	4285	8 5/8"	270'	none
Myrick Station		4449	4470	4 1/2"	4649'	none
Conglomerate Sand		4578	4596			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 260 sacks 60/40 pozmix cement with 10% gel and 500# hulls down
4 1/2" casing. Pumped 10 sacks 60/40 pozmix cement with 10% gel down
8 5/8" casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing, Inc. License No. _____

Address PO Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

John C. Niernberger (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 783188
Wichita, KS 67278-3188

SUBSCRIBED AND SWORN TO before me this 31st day of January, 2003

My Commission Expires: _____

KAREN HOPPER
Notary Public - State of Kansas
My Appt. Expires 10/27/03

15-179-20865-00-00


WELL LOG

Don E. Pratt
COMPANY P. O. Drawer 370
Hays, KS 67601
FARM BECKMAN NO. 3-31

SEC. 31 T. 10S R. 30W
LOC. 50' W SW SE SW

RIG. NO. 2
TOTAL DEPTH 4650'
COMM. 8-26-86 COMP. 9-5-86

COUNTY Sheridan
KANSAS



CONTRACTOR Murfin Drilling Company
250 N. Water, Suite 300
Wichita, KS 67202

CASING
20 10
15 8 -5/8" csg set @ 270' w/200 sx 60-40 Pozmix, 3% CC
12 6
13 5
4-1/2" csg set @ 4649' w/200 sx Common + 500 sx Lite.
ELEVATION PRODUCTION
FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Clay	140'
Shale	270'
Sand & Shale	2522'
Anhydrite	2550'
Shale & Shells	3365'
Shale & Lime (RTD)	4650'


RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

State of Kansas
County of Sedgwick } ss:

OCT 9 1986

I, Rob Ramseyer of the Murfin Drilling Company

upon oath depose that the above and foregoing is a true and correct copy of the log of the Beckman #3-31 well.



Rob Ramseyer
Rob Ramseyer, Agent for Operator
19 86

Subscribed and sworn to before me this 17th day of September
My Commission Expires 04-25-87

Eleanor Hall
Eleanor Hall NOTARY PUBLIC