

WELL PLUGGING RECORD

Give All Information Completely  
Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH

STITES #1.			
SE-SE-NE,			
Sec. 1-10, 23,			
Graham County, Ko.			

Locate well correctly on above  
Section Plat

Graham County. Sec. 1 Twp. 10 Rge. 23 (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE-SE-NE  
Lease Owner Harry Gore  
Lease Name Stites Well No. #1  
Office Address 400 Brown Bldg. Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-17 19 51  
Application for plugging filed 7-16 19 51  
Application for plugging approved 7-16 19 51  
Plugging commenced 7-17 1:00A.M. 19 51  
Plugging completed 7-17 6:30A.M. 19 51  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 4145' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Clay & soil		0	190'	8 5/8"	190'	none
Kansas KC.		3642	3871		dry	dry
Rose KC		3871	3981		dry	dry
Arbuckle		4110	4145		dry	dry

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 190 feet. Placed wood plug at 190', ran 1/2 sack hulla and 15 sacks cement. Filled hole with mud to 40 feet. Placed wood plug at 40 feet. Ran 1/2 sack hulla and 10 sacks cement, filling hole to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to Harry Gore  
Address 400 Brown Building Wichita, Kansas.

STATE OF KANSAS, COUNTY OF Ellis, ss.  
T.C. Strain (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) T.C. Strain

Rox 108, Hays, Kansas.  
(Address)

19th day of July, 19 51

STATE CORPORATION COMMISSION  
Notary Public.



PLUGGING  
FILE SEC. 1-10-R-23  
BOOK PAGE 43

JUL 23 1951  
07-23-1951

COMPANY: HARRY GORE

SE-SE-NE, Sec. 1,  
Twp. 10, Rge. 23,  
Graham County, Kansas.

LEASE: STITES #1.

ELEVATION: 2363 Derrick F.

NOTE: All meas. rotary bushings.

0 50 Clay & soil  
 50 70 Sand  
 70 190 Shells & blue shale  
 190 650 Shale  
 650 1005 Shale & shells  
 1005 1500 Shale & shells  
 1500 1670 Sand  
 1670 1675 Shale  
 1675 1700 Shale  
 1700 1930 Redbed  
 1930 1955 Anhydrite  
 1955 1970 Anhydrite  
 1970 2205 Redbed, shells & shale  
 2205 2385 Shale & shells  
 2385 2535 Shale  
 2535 2600 Shale  
 2600 2645 Lime  
 2645 2755 Shale & lime  
 2755 2905 Shale & lime  
 2905 3010 Shale & shells  
 3010 3075 Shale & lime  
 3075 3145 Shale & lime  
 3145 3185 Shale  
 3185 3165 Shale  
 3165 3325 Shale  
 3325 3410 Shale  
 3410 3505 Shale & lime  
 3505 3550 Lime & shale  
 3550 3610 Lime & shale  
 3610 3645 Lime & shale  
 3645 3690 Lime  
 3690 3730 Lime  
 3730 3744 Lime  
 3744 3770 Lime  
 3770 3815 Lime  
 3815 3850 Lime  
 3850 3885 Lime  
 3885 3935 Lime  
 3935 3970 Lime & Cong.  
 3970 4000 Conglomerate  
 4000 4040 Conglomerate  
 4040 4065 Conglomerate  
 4065 4105 Cong. Chert  
 4105 4110 Conglomerate  
 4110 4145 Arbuckle  
 4145 T.D. (rotary bushing meas.)

TOPS: (Geog. from rig floor)

Anhydrite	1930	Base KC	3871
Topeka	3895	Marmaton Cong	3981
Heebner	3609	Marm. sand	
Dodge	3633	zone	4044
Lansing KC.	3642	Cherty Congl	4068
	Arbuckle	4110	
	T.D.	4145	

CASING RECORD:

8 5/8" Surface Casing set at 190'  
w/150 sacks bulk cement. by Halliburton

D.S.T. by Johnston Testing Co.

3714'-3744' Tool open 1-1/2 Hrs.  
Recovered 140' slightly gas cut  
muddy salt water. Very weak in-  
termitten blow. B.H.P. 15 min.  
790#.

3825'-3850' Tool open 45 min.  
Recovered 15' rotary mud. B.H.P.  
0-very slight blow 3 min.

Ran Schlumberger Log to T.D.

COMMENCED: 7- 2-51  
COMPLETED: 7-17-51

STATE OF KANSAS ) SS  
COUNTY OF ELLIS )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Stites # 1, located SE-SE-NE, Sec.1, Twp.10, Rge.23, Graham County, Kansas.

PLUGGING

CONTRACTOR: Strain Drilling Company


WELL NO. 15-065-00197-23w  
BOOK 96 PAGE 43

By T.C. Strain  
T.C. Strain

07-23-1951

Subscribed and sworn to before me this 19 day of July, 1951

My Commission expires June 12, 1953



Mollie Washburn  
NOTARY PUBLIC.