

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 4 Twp. 10 Rge. 23 (E) (W) X
NE SW SE

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Imperial Oil Co.
Lease Name Rice Well No. #1
Office Address 2318 Washington, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 12-7-64 19____
Application for plugging approved _____ 19____
Plugging commenced 12-22-64 19____
Plugging completed 12-23-64 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4241' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
						709.97'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made plug back with sand to 3725', mixed and ran 5 sacks cement thru dump baler.
Squeezed hole with 20 sacks gel follow with 65 sacks cement, displaced with 5 sacks gel and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1964
12-28-1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24 day of December, 1964

My commission expires 24 October 1968

Sidney D. Miller
Notary Public.



15-065-03058-00-00

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1965

01-06-1965
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
903 Union National Bldg.
Wichita 2, Kansas

Rice Estate No. 1
NE SW SE Sec. 4-10S-23W
Graham County, Kansas

Total Depth: 4240'

Commenced: 10-9-56 Completed: 11-6-56 Elevation: 2451' R.B.
Production: 28 BOPD, 67% Water

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 196 feet with 150 sacks cement.

Figures indicate bottom of formations :

Sand & Clay	120'		
Shale & Shells	1180'		
Sand & Shale	1340'	Anhydrite	<u>TOPS</u> 2025' (/ 426)
Shale & Red Bed	1560'	Heebner	3723' (-1272)
Sand	1770'	Toronto	3743' (-1292)
Shale	1775'	Lansing	3758' (-1307)
Shale, Sand & Red Bed	2025'	Conglomerate	4223' (-1772)
Anhydrite	2060'	Total Depth	4240' (-1789)
Shale & Shells	2480'		
Shale & Lime	3747'		
Lime	3990'		
Conglomerate	4240'		
Total Depth	4240'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Raymond W. ...
Vice-President



Subscribed and sworn to before me this 16th day of November, 1956.

My Commission Expires:

April 18, 1959

Francis E. Basham
Notary Public