


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 4 Twp. 10S Rge. (E) 23 (W)

Location as "NE/CNW%SW%" or footage from lines C NW NE
Lease Owner K & E DRILLING, INC.
Lease Name COOK Well No. 1
Office Address 719 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed November 11 1960
Application for plugging filed November 11 1960
Application for plugging approved November 11 1960
Plugging commenced November 11 1960
Plugging completed November 11 1960
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4015 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	201'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First Halliburton plug set @ 400' w/1/2 sack hulls cemented w/20 sacks of cement through drill pipe
Second Halliburton plug set @ 200' w/1/2 sack hulls cemented w/20 sacks cement
Third Halliburton plug set @ 40' w/1/2 sack hulls cemented w/10 sacks cement to surface

RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1960
11-16-1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Clinton Engstrand (Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clinton Engstrand
Clinton Engstrand, President
719 Union Center Bldg., Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 15th day of November, 19 60

Wildalee Wind
Notary Public.

My commission expires October 30, 1961

15-065-00643-00-00

DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center Building
Wichita 2, Kansas

WELL NAME: #1 COOK
LOCATION: C NW NE
Section 4-10S-23W
Graham County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: November 4, 1960

CASING RECORD: 8-5/8" @ 201' w/160 sx.

COMPLETED: November 11, 1960
ELEVATION: 2448 DF 2450 KB

ROTARY TOTAL DEPTH: 4015'

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Surface soil and clay	50
Sand	130
Shale and shells	208
Sand and Shale	1350
Shale	1550
Sand	1750
Shale	1810
Shale and red bed	2088
Anhydrite	2180
Shale and shells	2230
Shale and shells	2560
Shale and lime	2775
Lime	2900
Lime and shale	3025
Lime	3275
Lime and shale	3410
Lime	4015

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1962
09-26-1962
CORPORATION DIVISION
Wichita, Kansas

CERTIFICATION


State of KANSAS }
County of SEDGWICK } ss:

I, Wayne L. Brinegar, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Wayne L. Brinegar
Wayne L. Brinegar

Subscribed and sworn to before me this 25th day of September, 1962.

Julene M. Bannon
Julene M. Bannon Notary Public.



Log originally filed on November 16, 1960

