


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Graham County. Sec. 5 Twp. 10 Rge. 23W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner C-G Drilling Co. & N. Appleman Company
Lease Name Clifford Well No. 1
Office Address 107 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 30 19 58
Application for plugging filed August 30 19 58
Application for plugging approved August 30 19 58
Plugging commenced August 31 19 58
Plugging completed August 31 19 58
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4030 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	213.50'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 600'. Set plug. Put in 20 sacks cement. Filled to 210'. Set plug. Put in 1/2 sack hulls and 20 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
G. F. Galloway 107 Rule Building
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of September, 19 58
My commission expires May 20, 1959

Vicky Jacobson
Vicky Jacobson Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
09-05-1958

PLUGGING SEP 5 1958
FILE SEC 5 T 10 R 23W
BOOK PAGE 127 LINE 37

15-065-00559-00-00

CONTRACTOR'S WELL LOG

OPERATOR C-G Drilling Co. & N. Appleman Co. WELL NAME Clifford #1
LOCATION SW SW NW SEC. 5-10-23 RIG NO. 1
COUNTY Graham STATE Kansas
COMMENCEMENT DATE August-23, 1958 COMPLETION DATE August 31, 1958

LOG OF WELL

Elevation 2446' kelly bushing.
All measurements taken from the top of kelly bushing.

Table with columns: FROM, TO, FORMATION, DEVIATION FROM VERTICAL, REMARKS. Rows include geological data such as Shale, Sand-Shale, Lime, and Shale-Shell with depth measurements and deviation notes.

CASING LEFT IN HOLE AFTER COMPLETION

Ran 213.50' (13 jts.) 8-5/8" OD Surface Casing.


STATE OF KANSAS }
COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By [Signature] G. F. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 3rd day of September, 1958.



My commission expires: May 20, 1959

[Signature] RECEIVED
Vicky Jacobs, Notary Public

PLUGGING
FILE SEC 5 T 10 R 23
BOOK PAGE 127 LINE 37

SEP 5 1958
CONSERVATION DIVISION
Wichita, Kansas