


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 5 Twp. 10 Rge. 23 (W) (W)
Location as "NE/CNW/SW" or footage from lines NE/4 NE/4 SW/4
Lease Owner Transit Corporation
Lease Name Clifford Well No. 1
Office Address 1516 Liberty Bank Building, Okla. City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 4-7 1956
Application for plugging filed 4-7 1956
Application for plugging approved 4-7 1956
Plugging commenced 4-7 1956
Plugging completed 4-7 1956
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4409 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	262'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 180 feet with heavy drilling mud, set plug and cemented with 15 sacks portland cement. Filled hole to 30 feet with heavy drilling mud, set plug, and cemented to bottom of cellar with 10 sacks cement.

04-17-1956
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
C. W. Dodson (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Dodson
Oklahoma City, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of April, 1956

My commission expires March 31, 1960

Frances C. Jerry
Notary Public.

PLUGGING
FILE SEC 5 T 10 R 23
BOOK PAGE 53 LINE 16

15-065 - 00858-00-00

TRANSIT CORPORATION

CLIFFORD #1

NE NE SW Section 5-10S-23W
Graham co., Kansas

Elevation: 2426 K.B.
Commenced: 3-23-56
Completed: 4-7-56

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Clay & Sand	0	130
Shale & Shells	130	400
Sand	400	520
Shale	520	650
Shale & Sand	650	730
Shale & Shells	730	1320
Shale & Sand	1320	1370
Shale & Shells	1370	1549
Sand	1549	1770
Shale & Shells	1770	2010
Anhydrite	2010	2050
Shale & Shells	2050	2365
Shale & Lime	2365	3680
Lime	3680	3990
Shale & Lime	3990	4088
Lime	4088	4112
Chert	4112	4134
Lime & Chert	4134	4169
Lime & Shale	4169	4193
Lime, Shale & Chert	4193	4318
Lime & Shale	4318	4358
Lime	4358	4409

Set 262' 8-5/8". Cemented with
215 sacks cement.

Total Depth

I hereby certify the foregoing to be a true and accurate Driller's Log
of the formations encountered in the above well.

PLUGGING			
FILE	SEC 5	T 10	R 23W
BOOK	PAGE 53	LINE 16	

TRANSIT CORPORATION

By C. W. Dodson
C. W. Dodson



Subscribed and sworn to before me this 12th day of April, 1956

Francis C. Jerry
Notary Public

My commission expires Mar. 31, 1960