


15-065-00859-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 5 Twp. 10 S Rge. 23 (X) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Sierra Petroleum Co., Inc.  
Lease Name Clifford Well No. 1  
Office Address 420 W. Douglas Ave., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 6/11/56 19  
Application for plugging filed 6/10/56 19  
Application for plugging approved 6/10/56 19  
Plugging commenced 6/11/56 19  
Plugging completed 6/11/56 19  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4005 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	204	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud 4005 to 200'. 200' Set wood plug with hulls and 15 sacks cement through drill pipe up to 170'. 170' up to 25' filled with heavy mud. 25' set wood plug with 1/2 sack hulls 5 sacks to cellar 0. Hole plugged at 11:30 p.m. 6/11/56


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.  
Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 13 day of June, 19 56  
My commission expires 1-30-57



Marge Cooper  
Notary Public.

PLUGGING  
FILE SEC 5 T 10 R 23W  
BOOK PAGE 71 LINE 2

RECEIVED  
06-14-1956  
CONSERVATION DIVISION  
WICHITA, KANSAS

15-065-00859-00-00

SIERRA PETROLEUM CO., INC.  
CLIFFORD #1

SE SE SW 5-10S-23W  
Graham County, Kansas

Total Depth: 4005'

Elev: 2407 DF

Comm: 6/1/56  
Comp: 6/11/56

Casing:

Cement:

8 5/8 @ 204'

with 140 sacks of Bulk

FORMATION	DEPTH
Surface clay	40
Sand	90
Clay & Shale	205
Shale (Blue)	815
Shale	1100
Sand & Pyrite	1275
Sand & shale	1400
Red bed & sand	1750
Red bed & shale	2005
Anhydrite	2045
Shale & shells	2260
Shale & Lime	3872
Lime	3944
Lime & shale	4005

Tops: Anhydrite	2005
Heebner	3714
Kansas City	3748
Base K. C.	3987

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

C. B. Honaker

Subscribed and sworn to before me this 13th day of June, 1956.

Margie Cooper  
Notary Public



My commission expires: 1-30-57.

PLUGGING  
FILE SEC 5 T 10 R 23W  
BOOK PAGE 71 LINE 2

06-14-1956