

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-63-0112800-00

API NUMBER 5-23-50

LEASE NAME BAUMGARTNER

WELL NUMBER # 2

SPOT LOCATION SE SE NE

SEC. 25 TWP. 9 RGE. 19 (E) or (W)

COUNTY ROOKS

Date Well Completed 5-13-50

Plugging Commenced 2-11-86

Plugging Completed 2-11-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR GRIGGS OIL, INC.

ADDRESS 105 N. Market Suite 800, WICHITA, KS.  
67202

PHONE (316) 267-7779 OPERATORS LICENSE NO. 5058

Character of Well ARBUCKLE  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? yes

Producing formation ARBUCKLE Depth to top 3623 bottom T.D. 3629'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Arbuckle</u>	<u>oil</u>	<u>3623</u>	<u>3629</u>	<u>10-3/4"</u>	<u>5-1-50</u>	
				<u>5 1/2"</u>	<u>5-13-50</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. SQZ CSG @ 2563. DID NOT DRILL OUT CEMENT. CEMENT @ 2500'. SQZ @ 800' to 1000'. PUMPED IN 5 1/2" CSG, 175 SX 60/40 POZ + 2 SX hulls. HOOKED UP 10 3/4" Surface pipe. Pumped in 75 SX 60/40 POZ w/ 3 SX hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied cement License No. \_\_\_\_\_  
Address Russell, KS.

STATE OF Kansas COUNTY OF ROOKS, ss.

RICK GRIGGS (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Rick A. Griggs

(Address) 105 N. Market. Suite 800

SUBSCRIBED AND SWORN TO before me this 24 day of February 1986

My Commission expires: August 25, 1988

Virginia Lee Smith  
Notary Public  
VIRGINIA LEE SMITH  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 8-25-88

FEB 26 1986

Form CP-4  
Revised 01-84